

Optimizing Material-Related Costs Using Dynamic Site Layout and Supply Chain Planning

Sarah Abou Dargham¹ | Sena Assaf¹ | Karim Faour² | Farook Hamzeh³


¹ Graduate Student, Civil and Environmental Engineering Department, American University of Beirut, Lebanon

² Civil Engineering Graduate, Civil and Environmental Engineering Department, American University of Beirut, Lebanon


³ Associate Professor, Civil and Environmental Engineering Department, University of Alberta, Canada

Presenting Co-Author: Sena Assaf

Outline



Introduction



Introduction

Seven groups
of resource
flow needed
to complete a
certain task

Construction Design

Components and **Materials**

Workers

Equipment

Space

Connecting Works

Addition to External Conditions

Right Time

Right Quantity

Desired Quality



**Cost Reduction
&
Value Addition**

Introduction

When Are Material-Related Costs Incurred on Site?

Material movement
into the site from
laydown areas or
storage facilities

Material transportation
to installation area

Push nature of activities

Introduction

Why Dynamic
Site Layouts?

Gap Statement

Different methods and models in the academic literature addressing material handling in a construction site have focused on:

- On-site congestion
- Logistics cost
- Project schedule
- Material flow to the site
- Dynamic site layout planning



The impact of how all those individual factors act and interact with one another in a single production system to incur material moving costs has been understudied.


Research Objective

How can we decrease material-related costs on site through the use of dynamic site layout and supply chain strategies?

What's the Main Problem?




Methodology



Case Study



GRC units Held on Rack




GRC Installation Zones

Case Study

Zone number	Number of GRC units (Q_{z_i} , $i = 1:8$)	Total GRC area per zone (m^2)	Installation period (weeks)
Zones 1,3,5	350	4550	8
Zones 2,4,6	700	9100	8
Zones 7,8	175	4550	6


GRC Quantities and Equivalent Areas per Zone



GRC Installation Schedule

Case Study

Available storage
area for GRC
units equivalent
to 100 units




Site Layout Plan


Conceptual Model

Bi-weekly
delivery per
zone




One delivery = $\frac{1}{4}$
of the quantity
per zone




Conceptual Model




Conceptual Model



Conceptual Model




Conceptual Model




On Site

Base Model



Base Model Concerns



Improved Model

Pull System

Decrease Lead Time
of Trucks on Site


- Decrease the # of trucks from 4 to 2
- Make deliveries weekly instead of biweekly

Merging Activities


Combine the
activities “Clean
GRC” and “Install
GRC” into one

- Crane moves a GRC rack (10 units) instead of moving one unit
- Labors of both activities should work at the same time
- Requires less time than if the activities were separated (less movement)

Improved Model



Developed Models



Assessment Criteria

Total hours

Model simulation time

The Truck Delay Cost (\$)

Cost incurred by trucks waiting to be unloaded instead of performing another delivery

Deterioration Cost (\$)

Cost of the total time a GRC unit spends on site before its final installation


Turnover Rate (hours/occurrence)

Time needed for the storage space on site to be replenished by a new GRC rack.


Total Cost (\$)

Cost of the trucks, labour, crane, the GRC units' deterioration cost, and truck delay cost.

Simulation Results & Analysis



Simulation Results & Analysis



Simulation Results & Analysis

Reducing Lead Time Effect

Decreased transportation delay cost

Satisfy site and schedule demand

Reduced site congestion

Combining Activity Effect

Decrease unneeded movement

Decreased total material handling cost

Increased space utilization

Conclusions & Future Work

Incorporating lean tools along with the proper supply chain

- > Reduced the material related costs on site by 15-16%
- > Reduced the process time by 15%

Future work aims at improving the existing model to better reflect the actual site conditions regarding labour productivity and truck capacity of the site.

Thank you for your time!

